



CONSTRUCTION SEQUENCE		
STEP	PHASE	DESCRIPTION
1	PERMITTING	RECEIVE NPDES COVERAGE FROM SCDHEC. (MAINTAIN ONSITE AT ALL TIMES)
2	PERMITTING	RECEIVE CAA APPROVAL AND APPROVED PLANS FROM BERKELEY COUNTY. (MAINTAIN ONSITE AT ALL TIMES)
3	PRE CONSTRUCTION	FLAG: WORK LIMITS, TREE BARRICADE LOCATIONS, BUFFER AREA PROTECTION DELINEATIONS AND SILT FENCE LAYOUT.
4	PRE CONSTRUCTION	HOLD PRECONSTRUCTION CONFERENCE AT LEAST FORTY-EIGHT(48) HOURS PRIOR TO STARTING CONSTRUCTION.
5	PRE CONSTRUCTION	REVIEW TEMPORARY DIVERSION DITCH PLAN, TREE PROTECTION AND PERIMETER CONTROLS WITH SITE INSPECTOR. TAKE PICTURES OF ALL PROTECTED TREES AND LOCATIONS WHERE SITE WORK TIES INTO EXISTING TO DOCUMENT PREDEVELOPMENT CONDITIONS.
6	PRE CONSTRUCTION	NOTIFY SCDHEC EQC OR OCRM OFFICE 48 HOURS PRIOR TO BEGINNING LAND-DISTURBING ACTIVITIES.
7	SWPPP INITIAL	INSTALL CONSTRUCTION EXITS/ENTRANCES.
8	SWPPP INITIAL	PERFORM CLEARING AND GRUBBING AS NECESSARY FOR INSTALLATION OF PERIMETER EROSION CONTROL MEASURES.
9	SWPPP INITIAL	INSTALLATION OF PERIMETER CONTROLS. (SILT FENCE, ETC.)
10	SWPPP INITIAL	PERFORM CLEARING AND GRUBBING OF THE FOLLOWING AREAS: SEDIMENT BASINS, TEMPORARY DIVERSIONS.
11	SWPPP INITIAL	CONSTRUCT SEDIMENT BASINS, OUTFALL STRUCTURES, TEMPORARY DIVERSIONS. BEGIN CLEARING AND GRUBBING FOR LAY DOWN AREAS AND STOCK PILE LOCATIONS.
12	SWPPP CONSTRUCTION	CLEARING AND GRUBBING OF THE REMAINDER OF THE APPROVED LIMITS OF DISTURBANCE.
13	SWPPP CONSTRUCTION	ROUGH GRADE SITE.
14	SWPPP CONSTRUCTION	INSTALL STORM DRAIN SYSTEM AND UTILITIES. PLACE INLET PROTECTION AS EACH STORM INLET IS INSTALLED. INSTALL RIPRAP WHERE SHOWN ON THE APPROVED PLANS, AS SOON AS PRACTICAL.
15	SWPPP CONSTRUCTION	COMPLETE FINE GRADING, INSTALL CURB, GUTTER AND PAVEMENT.
16	SWPPP STABILIZATION	REPLACE INLET PROTECTION AS NEEDED FOR SURFACE COURSE INSTALLATION.
17	SWPPP STABILIZATION	CLEAN-OUT AND REMOVE CONCRETE WASHOUT.
18	SWPPP STABILIZATION	COMPLETE PERMANENT / FINAL STABILIZATION.
19	SWPPP STABILIZATION	CLEAN-OUT TEMPORARY SEDIMENT BASINS.
20	SWPPP STABILIZATION	REMOVAL OF TEMPORARY SEDIMENT AND EROSION CONTROL MEASURES AFTER THE ENTIRE AREA DRAINING TO THE STRUCTURE IS FINALLY STABILIZED.
21	SWPPP STABILIZATION	PERFORM AS-BUILT SURVEYS OF DETENTION STRUCTURES AND SUBMIT TO MS4 FOR ACCEPTANCE.
22	POST CONSTRUCTION	SUBMIT NOTICE OF TERMINATION (NOT) TO SCDHEC.